

TESTPASSPORT

練習題



質 量 更 高

服 務 更 好

<https://www.testpassport.net>

免費一年更新服務

Exam : DCDC-004

**Title : BICSI Data Center Design
Consultant (DCDC)**

Version : DEMO

1.What room should have its own dedicated air handling system apart from the computer room?

- A. Electrical Room
- B. Break Room
- C. Printer Room
- D. Storage Room
- E. Telecommunications Room

Answer: C

2.What is the recommended amount of fuel supply needing to be available to a class F2 data center?

- A. 12 hours
- B. 18 hours
- C. 24 hours
- D. 30 hours
- E. 36 hours

Answer: C

3.What is the minimum size conductor from the TMGB to the building main ground bus?

- A. 80mm (150MCM) bare copper
- B. 100mm (200MCM) bare copper
- C. 130mm (250MCM) bare copper
- D. 160mm (300MCM) bare copper
- E. 200mm (400MCM) bare copper

Answer: C

4.What is the minimum distance from the bottom of the access floor to the top of the cable tray?

- A. 1 inch
- B. 2 inches
- C. 3 inches
- D. 4 inches
- E. 5 inches

Answer: B

5.What is the distance from the bottom of the access floor to the bottom of the cable tray?

- A. 6 inches
- B. 7 inches
- C. 8 inches
- D. 9 inches
- E. 10 inches

Answer: C